

**THE CORPORATION OF TAY VALLEY TOWNSHIP
TENDER FOR IMPROVEMENTS TO UNOPENED ROAD ALLOWANCE BETWEEN
CONCESSION 8 & 9 (MABERLY)**

CONTRACT #2020-PW-010

ADDENDUM NO. 1

**THIS ADDENDUM SHALL BE INCORPORATED INTO THE TENDER PACKAGE
AND SHALL FORM PART OF THE CONTRACT DOCUMENTS**

Date Issued: April 23, 2020
Issued By: Amanda Mabo, Clerk

Please note the following changes, corrections, additions, deletions, information and/or instructions in connection with the Tender Package. Failure to acknowledge receipt of this Addendum as per Part "A" – Information to Bidders may render your submission non-responsive.

This addendum is to address the following questions and/or clarification:

Clarification:

Please note that item number 7 and item number 8 have been revised to the following:

7	SP	Min. 25-Tonne Excavator, or Equivalent, w/ Hoe Ram Attachment and Operator	15	hr.	\$ _____	\$ _____
8	SP	Min. 25-Tonne Excavator, or Equivalent, w/ Bucket Attachment and Operator	10	hr.	\$ _____	\$ _____

All references to "335 CAT Excavator" or "332 Cat Excavator" in "Part C" of the Tender shall be substituted with "Min. 25-Tonne Excavator"

Please find attached updated bid sheet that is to replace the original bid sheet and included in "Part D" of the bid submission.

End of Addendum No. 1

Amanda Mabo, Clerk
clerk@tayvalleytpw.ca

**THE CORPORATION OF TAY VALLEY TOWNSHIP
TENDER FOR IMPROVEMENTS TO UNOPENED ROAD ALLOWANCE BETWEEN
CONCESSION 8 & 9 (MABERLY)**

CONTRACT #2020-PW-010

PART “D” – FORM OF TENDER

I/We hereby agree to provide section rehabilitation services in accordance with the provisions set out in Parts “A”, “B”, and “C” of this Tender, for the following firm prices. Exact location is identified in “Schedule “A” – Location Map”.

Item No.	Spec. No.	Description	Estimated Quantities	Unit	Bid Price Per Unit	Total Bid
1	SP	Site Preparation	1	L.S.	\$ _____	\$ _____
2	SP	Earth Excavation – Stripping	600	m ²	\$ _____	\$ _____
3	314 501 SP	Granular ‘B’-Quarry Sourced	200	T	\$ _____	\$ _____
4	314 501 SP	Granular ‘A’-Quarry Sourced	200	T	\$ _____	\$ _____
5	421 SP	Install 400 mm CSP, 2.8 mm, Polymer Laminated	12	m	\$ _____	\$ _____
6	421 SP	Install 300 mm CSP, 2.0 mm, Entrance Culvert – PROVISIONAL	9	m	\$ _____	\$ _____
7	SP	Min. 25-Tonne Excavator, or Equivalent, w/ Hoe Ram Attachment and Operator	15	hr.	\$ _____	\$ _____
8	SP	Min. 25-Tonne Excavator, or Equivalent, w/ Bucket Attachment and Operator	10	hr.	\$ _____	\$ _____
9	SP	Tandem Truck w/ Operator	10	hr.	\$ _____	\$ _____
Total Tendered Price						\$ _____

Notes:

- i) H.S.T. will be paid in addition to the tendered price.
- ii) Prices must be rounded to two decimal places only.
- iii) OPSS.MUNI specifications shall apply when applicable.